



Ref No: 054/2024/PMID/MCWAP2/RFB Addendum No.:40

22 July 2024

**ABSTRACTION WORKS, PUMPING STATIONS, RESERVOIRS, PIPELINE, RELATED  
MULTIDISCIPLINE WORKS, ANCILLARY WORKS**

**ADDENDUM NO.:40**

Herewith please find Addendum No.:40 which forms an integral part of the above-mentioned contract.

**PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM AS FOLLOWS:**

- 1. Complete the section below and **without delay** email a copy of this page to TCTA, email address tenders01@tcta.co.za; for the attention of The Receiving Officer to confirm that you have received this addendum.

Regards

.....  
**Azwi Nelwamondo**  
**Senior Manager: Procurement**

---

I/We herewith acknowledge receipt of ADDENDUM NO.:40 for CONTRACT NO. 054/2024/PMID/MCWAP2/RFB

SIGNATURE: ..... DATE: .....

ON BEHALF OF: .....

## ADDENDUM NO.:40

### **1. PART C3.1 SPECIFICATION SECTION 9, MEASUREMENT AND PAYMENT ITEM 9.001 TO READ AS FOLLOWS:**

#### **9.001 Excavation in all materials to spoil Unit: cubic metre (m3)**

Measurement will be the net solid volume of the excavated item calculated from the lines and levels given on the Drawings and agreed ground level surveys, based on a vertical payment line. A distinction will be made for the various locations of excavation. Separate measurement will be made for bulk and restricted excavation as well as for carrying out additional controlled excavations in areas where foundation conditions are deemed by the Engineer to be inadequate.

No material excavated in excess of the payment line will be measured for payment, notwithstanding the tolerances in workmanship allowed. The Contractors rates should include for possible overbreak, geotechnical conditions, safe excavation side slopes, shoring if required, etc.

The rate shall include full compensation for all work required to excavate in all materials, including excavation in stages where required, trimming and preparation of exposed surfaces and foundation surfaces, any overbreak, loading and hauling within the free haul distance the excavated material to the designated borrow and spoil areas or temporary stockpiles. It also includes temporary support of excavated surfaces and subsequent removal and disposal of temporary support, scaling down excavated surfaces and removal of loose material and any protective measures provided. No payment will be made for overbreak.

For grout waste material that results from grouting operations, the excavation of the solidified grout waste will be measured as bulk excavations in m3. The rate of excavation shall include full compensation for all work required to excavate the solidified grout, loading and hauling within the free haul distance on site, as well as haulage and spoiling of the excess waste material for disposal at an authorised dump site, inclusive of all labour, plant, material, fuel or other associated costs. The rate must also include temporary embankments, holding ponds or excavated surfaces / trenches and subsequent removal of such containment areas, and the required reinstatement of such

areas. Moreover, all activities and operations must fully comply with all the environmental requirements as per the contract.