

REF NO: 054/2024/PMID/MCWAP2/RFB NOTICE 69

11 JULY 2024

***ABSTRACTION WORKS, PUMPING STATIONS, RESERVOIRS, PIPELINE, RELATED
MULTIDISCIPLINE WORKS, ANCILLARY WORKS***

Dear Bidder,

TCTA acknowledges receipt of the requests for clarification listed in the attached table. The response to each request for clarification is provided in the attached table.

Yours faithfully

Azwi Nelwamondo
Senior Manager: Procurement

NO.	REQUESTS FOR CLARIFICATION	TCTA RESPONSES
1	<p>TCTA responded on notice#42 no. 12 as follows: “Suction scours: - HLS1.11 on HLS1.8 - HLD1.13 on HLD1.8” HLD1.13 and HLD1.8 are both valves and are located on the delivery side. The contractor seeks confirmation if one drain valve (HLD1.13) installed on Item HLD1.12 is correct?</p>	<p>HLD1.13 is a single scour valve to be installed on HLD1.12. No additional scours are required on the delivery side of the pump station.</p> <p>HLD1.8 is an isolation valve to enable isolation of air valve (HLD1.9).</p>
2	<p>C314 - Environmental Management P2V3 4.7.5 Environmental Monitoring Variables The Contractor must make provision for a 5 m high shade netting (80% shade) in all noise, dust, and visual, sensitive areas to reduce dust fallout, visual, and noise impacts on sensitive receptors such as Kesarona Primary School, game breeding and hunting areas.</p> <p>Could the Employer indicate the specification or provide similar pictures of “5 m high shade netting (80% shade)” ?</p>	<p>Refer to Notice # 65 Item 4</p>